

Phase 3 Buildings 162 and 163 Flooring Scope Of Work (Common Spaces and Bedrooms)

Furnish and install LVT over existing flooring and demo existing cove base, furnish and install 6" Cove Base in one building – (72 Apartment Units)

- LVT - ID LATITUDE (Color TBD) 80,692 sq ft
 - Tarkett ID Latitude LVT Tile + Plank
 - ASTM F1700 Class III Type B
 - Total Thickness 0.120" (3.0 mm)
 - Wear Layer Thickness: 20 mill (0.50 mm)
 - Finish: Techtonic
 - Edge Treatment: Square Edge
 - Limited Warranty: 20 year
 - LVT Adhesive
 - 6" Cove Base removal, supply and install new 6" Cove Base
 - Vinyl Cove Base 1/8" roll 40 black toe
 - Wall Base Adhesive
 - Slab Prep and LVT Installation – 80,692 Sq Ft
- Replace Entry Door thresh-hold
- Remove and Replace furniture
 - Moisture testing

Contact: Julius Gay
POM, Maintenance Superintendent
(850) 599-8054

Post date: Wednesday, January 18, 2023
Closing date: Wednesday, January 25, 2023

Email Proposals to Germarlon.hall@famu.edu or Purchasing@famu.edu